

# GOVERNMENT OF KHYBER PAKHTUNKHWA

## IRRIGATION DEPARTMENT



### Technical Bidding documents.

For Solar system in Kohat Irrigation Division Kohat. For the following Projects.

**For the Month of 19.05.2022 and 23.05.2022.**

Sl No.	Name of work and sub work.	Discharge. (GPH).	Head (ft)	Setting. (ft)	Estimated cost. (M).
	ADP No.1199-200154- KARAK AREA DEVELOPMENT PROJECT (KADP).				
A.	NIT No.1, Date of Opening. 19.05.2022.				
1	Solarization on existing Du well at Mohalla Meta khel-I District Karak.	4000	107	94	1.50
2.	Solarization on existing tubewell at (Mohala Yousaf Khel) Sabir Abad Karak.	5700	210	171	2.50
3.	Solarization on existing tubewell at Mohala Bazid Khel GMK Khel District Karak.	5700	210	171	2.50
4.	Solarization on existing Tubewell at (Mohala Tapi Algadi) district Karak.	4150	175	164	2.00
5.	Solarization on existing Dug well at (Mohala) Mata Khel-II karak.	4000	108	84	1.50
6.	Solarization on existing Dug well at Mashal Teri-I District Karak.	4000	183	151	2.00
7	Solarization on existing Dub well at Kamanri Palosa Sar Karak.	4000	107	94	1.50
8	Solarization on existing Dubwell at Sher Khan Kala-I District Karak	5990	126	103	2.00
9	Solarization on existing Dubwell at Shawal Adda district Karak.	5340	140	119	2.00
10	Solarization on existing Dubwell at Bagu Khel-II Distt: Karak.	5650	166	146	2.50
11	Solarization on existing Dubwell at Garori char Khel Distt: Karak.	4445	166	139	2.00
12	Solarization on existing Dubwell at Samay New Abadi Sabir Abad District Karak.	4100	180	139	2.00
13	Solarization on existing Dubwell at Ghebal Wanay Talab Khel District Karak.	4425	166	147	2.00
14	Solarization on existing Dubwell at Sher Khan Kala-II District Karak.	5070	146	135	2.00
15	Solarization on existing Tubewell at Tehran Koi District Karak.	4000	182	159	2.00
16	Solarization on existing Dubwell at Meta Khel-III Distt: Karak.	4100	180	139	2.00
17	Solarization on existing Dubwell at Ghundi Shahbaz Khan-I District Karak.	4330	170	143	2.00
18	Solarization on existing Dubwell at Kabir Kala-I Distt: Karak.	4415	166	147	2.00
19	Solarization on existing Dubwell at Sarat Khel District Karak.	4000	72	52	1.00
20	Solarization on existing Dubwell at Dab Sangini Distt: Karak.	4415	166	147	2.00
21	Solarization on existing Dubwell at Esak Chuntra-I Distt: Karak.	4415	166	147	2.00
22	Solarization on existing Dubwell at Sher Khan Kala-III Karak.	4415	166	147	2.00
23	Solarization on existing Dubwell at Bagu Khel-III, Karak.	4415	166	147	2.00
24	Solarization on existing Dubwell at Levo Algadi Karak.	5600	133	123	2.00
25	Solarization on existing Dubwell at Metakhel-IV, Distt: Karak.	4600	160	143	2.00
26	Solarization on existing Dubwell at Talab Khel-I District Karak.	6400	118	103	2.00
B.	NIT No.2, date of opening 23.05.2022.				
27	Solarization on existing Dubwell at Pashi Khel District Karak.	5130	145	127	2.00
28	Solarization on existing Dubwell at Sabir Abad-I District Karak.	5120	145	131	2.00
29	Solarization on existing Tubewell at Kamali Zara Khel Distt: Karak	4165	220	190	2.50
30	Solarization on existing Dubwell at Kabir Kala-II Distt: Karak.	6000	125	115	2.00
31	Solarization on existing Dubwell at Chogono Sabir Abad Karak.	4090	105	94	1.50
32	Solarization on existing Dubwell at Mangar Khel District Karak.	6800	140	118	2.50
33	Solarization on existing Dubwell at Same Sabir Abad-II Karak.	5650	133	111	2.00

34	Solarization on existing Dubwell at Garori Char Khel-I Distt:Karak.	6800	112	91	2.00
35	Solarization on existing Dubwell at Garori Char Khel-II, Karak.	6800	111	103	2.00
36	Solarization on existing Dubwell at Toor March Distt: Karak.	4540	162	143	2.00
37	Solarization on existing Dubwell at Gul Banda Distt: karak.	5310	140	127	2.00
38	Solarization on existing Dubwell at Biland Kala-I Distt: Karak.	6400	118	103	2.00
39	Solarization on existing Tubewell at Bilan Kala-II distt: Karak.	6000	126	103	2.00
40	Solarization on existing Dubwell at Talab Khel-II, distt: Karak.	6000	125	115	2.00
41	Solarization on existing Dubwell at Bilal Khel Distt: Karak.	4545	162	143	2.00
42	Solarization on existing Dubwell at Mohabat Khel Distt: Karak.	5040	149	111	2.00
43	Solarization on existing Dubwell at Kabir Kala-III Distt: Karak.	6365	119	99	2.00
44	Solarization on existing Dubwell at Mohala kabir Kala-IV Karak.	6400	118	103	2.00
45	Solarization on existing Dubwell at Jama Kala Karak-I.	6000	126	103	2.00
46	Solarization on existing Dubwell at Bagu Khel-IV, Distt: Karak.	4540	162	143	2.00
47	Solarization on existing Dubwell at Metha Khel-V, Distt: Karak.	4540	162	143	2.00
48	Solarization on existing Dubwell at Biland Kala-III, distt: Karak.	5700	133	99	2.00
49	Solarization on existing Dubwell at Aya Khel District Karak.	5020	150	107	2.00
50	Solarization on existing Dubwell at Sher Khan Kala-IV Distt: karak.	6900	110	95	2.00
51	Solarization on existing Dubwell at Jama Kala-II, Distt: Karak.	5070	147	123	2.00
52	Solarization on existing Tubewell at Sabir Abid-II, district Karak.	5700	164	149	2.50
53	Solarization on existing Tubewell at Chokara-I PK86 Distt Karak.	4000	230	182	2.50

**Issued to.....**

**Kohat Irrigation Division Kohat.**

**Appendix A to  
Instructions to Bidders**

## **NAME OF ELIGIBLE COUNTRIES**

All countries of the World with whom Islamic Republic of Pakistan has commercial relations, in Construction Sector.

**EVIDENCE OF BIDDER'S CAPABILITY**

**SYSTEM DESIGN FOR MANUAL TRACKING BASED SOLAR POWER PUMPING SETS**

S No.	Name of Work	Discharge (l-GPH)	Head (Feet)	Setting (feet)	Water Horse Power (KW)	Pump efficiency	Motor Efficiency	Motor Input Power (watt)	Shaft Power (Watt)	Total PV Power (Watt)	PV Generator Peak Power (watts)				PV De-Rating Factor for Solar Panels as per Specification attached
											No of Strings in Parallel	No of Module/String in Series	Module Size	Total PV Generation	
	ADP No.1199-200154- KARAK AREA DEVELOPMENT PROJECT (KADP).														
A.	NIT No.1, Date of Opening. 19.05.2022.														
1	Solarization on existing Du well at Mohalla Meta khel-I District Karak.	4000	107	94											
2.	Solarization on existing tubewell at (Mohala Yousaf Khel) Sabir Abad Karak.	5700	210	171											
3.	Solarization on existing tubewell at Mohala Bazid Khel GMK Khel District Karak.	5700	210	171											
4.	Solarization on existing Tubewell at (Mohala Tapi Algadi) district Karak.	4150	175	164											
5.	Solarization on existing Dug well at (Mohala) Mata Khel-II karak.	4000	108	84											
6.	Solarization on existing Dug well at Mashal Teri-I District Karak.	4000	183	151											

7	Solarization on existing Dub well at Kamanri Palosa Sar Karak.	4000	107	94											
8	Solarization on existing Dubwell at Sher Khan Kala-I District Karak	5990	126	103											
9	Solarization on existing Dubwell at Shawal Adda district Karak.	5340	140	119											
10	Solarization on existing Dubwell at Bagu Khel-II Distt: Karak.	5650	166	146											
11	Solarization on existing Dubwell at Garori char Khel Distt: Karak.	4445	166	139											
12	Solarization on existing Dubwell at Samay New Abadi Sabir Abad District Karak.	4100	180	139											
13	Solarization on existing Dubwell at Ghebal Wanay Talab Khel District Karak.	4425	166	147											
14	Solarization on existing Dubwell at Sher Khan Kala-II District Karak.	5070	146	135											
15	Solarization on existing Tubewell at Tehran Koi District Karak.	4000	182	159											
16	Solarization on existing Dubwell at Meta Khel-III Distt: Karak.	4100	180	139											

17	Solarization on existing Dubwell at Ghundi Shahbaz Khan-I District Karak.	4330	170	143											
18	Solarization on existing Dubwell at Kabir Kala-I Distt: Karak.	4415	166	147											
19	Solarization on existing Dubwell at Sarat Khel District Karak.	4000	72	52											
20	Solarization on existing Dubwell at Dab Sangini Distt: Karak.	4415	166	147											
21	Solarization on existing Dubwell at Esak Chuntra-I Distt: Karak.	4415	166	147											
22	Solarization on existing Dubwell at Sher Khan Kala-III Karak.	4415	166	147											
23	Solarization on existing Dubwell at Bagu Khel-III, Karak.	4415	166	147											
24	Solarization on existing Dubwell at Levo Algadi Karak.	5600	133	123											
25	Solarization on existing Dubwell at Metakhel-IV, Distt: Karak.	4600	160	143											
26	Solarization on existing Dubwell at Talab Khel-I District Karak.	6400	118	103											

B.	NIT No.2, date of opening.23.05.2022.														
27	Solarization on existing Dubwell at Pashi Khel District Karak.	5130	145	127											
28	Solarization on existing Dubwell at Sabir Abad-I District Karak.	5120	145	131											
29	Solarization on existing Tubewell at Kamali Zara Khel Distt: Karak	4165	220	190											
30	Solarization on existing Dubwell at Kabir Kala-II Distt: Karak.	6000	125	115											
31	Solarization on existing Dubwell at Chogono Sabir Abad Karak.	4090	105	94											
32	Solarization on existing Dubwell at Mangar Khel District Karak.	6800	140	118											
33	Solarization on existing Dubwell at Same Sabir Abad-II Karak.	5650	133	111											
34	Solarization on existing Dubwell at Garori Char Khel-I Distt:Karak.	6800	112	91											
35	Solarization on existing Dubwell at Garori Char Khel-II, Karak.	6800	111	103											



36	Solarization on existing Dubwell at Toor March Distt: Karak.	4540	162	143											
37	Solarization on existing Dubwell at Gul Banda Distt: karak.	5310	140	127											
38	Solarization on existing Dubwell at Biland Kala-I Distt: Karak.	6400	118	103											
39	Solarization on existing Tubewell at Bilan Kala-II distt: Karak.	6000	126	103											
40	Solarization on existing Dubwell at Talab Khel-II, distt: Karak.	6000	125	115											
41	Solarization on existing Dubwell at Bilal Khel Distt: Karak.	4545	162	143											
42	Solarization on existing Dubwell at Mohabat Khel Distt: Karak.	5040	149	111											
43	Solarization on existing Dubwell at Kabir Kala-III Distt: Karak.	6365	119	99											
44	Solarization on existing Dubwell at Mohala kabir Kala-IV Karak.	6400	118	103											
45	Solarization on existing Dubwell at Jama Kala Karak-I.	6000	126	103											

46	Solarization on existing Dubwell at Bagu Khel-IV, Distt: Karak.	4540	162	143											
47	Solarization on existing Dubwell at Metha Khel-V, Distt: Karak.	4540	162	143											
48	Solarization on existing Dubwell at Biland Kala-III, distt: Karak.	5700	133	99											
49	Solarization on existing Dubwell at Aya Khel District Karak.	5020	150	107											
50	Solarization on existing Dubwell at Sher Khan Kala-IV Distt: karak.	6900	110	95											
51	Solarization on existing Dubwell at Jama Kala-II, Distt: Karak.	5070	147	123											
52	Solarization on existing Tubewell at Sabir Abid-II, district Karak.	5700	164	149											
53	Solarization on existing Tubewell at Chokara-I PK86 Distt Karak.	4000	230	182											

**Application Form A – 1**

**General Information**

*All individual firms and each partner of a joint venture applying for qualification are requested to complete the information in this form. Nationality information is also to be provided for foreign owners or applicants who are forming part of the Joint Ventures as required under the PEC Bye-Laws as a Partnership/Joint Venture.*

*Where the Applicant proposes to use named subcontractors for critical components of the works or for work contents in excess of 10 percent of the value of the whole works, the following information should also be supplied for the specialist subcontractor(s).*

1.	Name of Firm	
2.	Head Office Address	
3.	Telephone	Contact Person: Name: Title:
4.	Fax	
5.	Place of Incorporation/Registration	Year of Incorporation/Registration

<b>NATIONALITY OF OWNERS</b>		
<b>NAME</b>		<b>NATIONALITY</b>
1.		
2.		
3.		
4.		
5.		

**Application Form A – 2****General Experience Record**

Name of Applicant or partner of a joint venture
---

*All individual firms and all partners of a joint venture are requested to complete the information in this form. The information supplied should be the annual turnover of the Applicant (or each member of a joint venture), in terms of the amounts billed to clients for each year for work in progress or completed over the past five years.*

*Use a separate sheet for each partner of a joint venture.*

<b>Annual Turnover</b>		
<b>Year</b>	<b>Turnover (in actual currency)</b>	<b>Equivalent Rupees in Millions</b>
1.		
2.		
3.		
4.		
5.		

**Application Form A - 3**

**Joint Venture Summary**

<b>Names of all Partners of a Joint Venture</b>	
1.	Lead Partner
2.	Partner
3.	Partner

*Total value of annual turnover, in terms of work billed to clients,*

<b>Annual Turnover Data (Equivalent in Pak Rupees, Millions)</b>						
<b>Partner</b>	<b>Form A-2 Page No.</b>	<b>Year 1</b>	<b>Year 2</b>	<b>Year 3</b>	<b>Year 4</b>	<b>Year 5</b>
1. Lead Partner						
2. Partner						
3. Partner						
<b>Total:</b>						

## Application Form A – 4

### Particular Experience Record

*Name of Applicant or partner of a joint venture*

*On a separate page, using the format of Application Form A-5, each applicant or partner of a Joint Venture is required to list all contracts of a value equivalent to Pak **Rupees 10 million** and above of a similar nature and complexity (Supply & Installation of Solar Based Pumping Machinery in any Public Work/NGOs) to the contract for which the Applicant wishes to qualify, undertaken during the last five years. The information is to be summarized, using Application Form A-5, for each contract completed or under execution by the Applicant or by each partner of a Joint Venture.*

*Where the Applicant proposes to use named subcontractor(s) for critical components of the works or for work contents in excess of 10 percent of the value of the whole works, the information in the afore-mentioned forms should also be supplied for each specialist subcontractor.*

**Application Form A – 5  
Details of Contracts of Similar Nature & Complexity**

*Name of Applicant or partner of a joint venture*

Use a separate sheet for each contract.

1.	Name of Contract
	Country
2.	Name of Employer
3.	Employer Address.....
4.	Nature of works and special features relevant to the contract for which the Applicant wishes to pre-qualify ..... .....
5.	Contract Role (Tick One) (a) Sole Contractor                      (b) Sub- Contractor                      (c) Partner in a Joint Venture
6.	Value of the total contract (in specified currencies) at completion, or at date of award for current contract  Currency .....                      Currency .....                      Currency .....
7.	Equivalent in Pak/Rs.
8.	Date of Award
9.	Date of Completion
10.	Contract Duration (Years and Months)  _____ Years                      _____ Months
11.	Specified Requirements <sup>1</sup> ..... ..... .....

<sup>1</sup>Insert any specific criteria required for particular operations, such as annual volume of earthmoving, underground excavation, or placing concrete etc.

**Application Form A – 6****Summary Sheet: Current Contract Commitments/Works in Progress**

<i>Name of Applicant or partner of a joint venture</i>
--

*Applicants and each partner to an application should provide information on their current commitments on all contracts that have been awarded, or for which a letter of intent or acceptance has been received, or for contracts approaching completion, but for which substantial Completion Certificate has yet to be issued.*

<b>Name of Contract</b>	<b>Value of Outstanding work (Equivalent Pak Rs. Millions)</b>	<b>Estimated Completion Date</b>
1.		
2.		
3.		
4.		
5.		
6.		



**Application Form A – 7**

**Personnel Capabilities**

<i>Name of Applicant</i>
--------------------------

*For specific positions essential to contract implementation, Applicants should provide the names of at least two candidates qualified to meet the specified requirements stated for each position. The data on their experience should be supplied on separate sheets using one Form for each candidate (Application Form A-8).*

1.	Title of Position
	Name of Prime Candidate
	Name of Alternate Candidate
2.	Title of Position
	Name of Prime Candidate
	Name of Alternate Candidate
3.	Title of Position
	Name of Prime Candidate
	Name of Alternate Candidate
4.	Title of Position
	Name of Prime Candidate
	Name of Alternate Candidate

**Application Form A – 8**

**Candidate Summary**

<i>Name of Applicant</i>
--------------------------

<b>Position</b>	<b>Candidate</b> [Tick appropriate one]  <input type="checkbox"/> Prime <input type="checkbox"/> Alternate	
Candidate information	1. Name of Candidate	2. Date of Birth
	3. Professional Qualification	4. PEC Registration No.
Present employment	5. Name of employer	
	Address of employer	
	Telephone	Contact (manager/personnel officer)
	Fax	
	Job title of candidate	Years with present employer

*Summarize professional experience over the last 10 years, in reverse chronological order. Indicate particular technical and managerial experience relevant to the Project.*

Month/ Dates/Years		Company/Project/Position/Relevant technical and management experience
From	To	

**Application Form A - 9  
Equipment Capabilities**

*Name of Applicant*

*The Applicant shall provide adequate information to demonstrate clearly that he has the capability to meet the requirements for each and all items of equipment listed in the Evaluation Criteria 1.2 (v). A separate Form shall be prepared for each item of equipment listed or for alternative equipment proposed by the Applicant.*

<b>Item of Equipment</b>		
Equipment information	1. Name of manufacturer	2. Model and power rating
	3. Capacity	4. Year of manufacture
Current status	5. Current location	
	6. Details of current commitments	
Source	7. Indicate source of the equipment  <input type="checkbox"/> Owned <input type="checkbox"/> Rented <input type="checkbox"/> Leased	

*Omit the following information if it is owned by the Applicant or partner.*

Owner	8. Name of owner	
	9. Address of owner	
	Telephone	Contact name and title
	Fax	
Agreement	Details of rental/lease specific to the Project	

## Application Form A - 10 Financial Capability

### ***Name of Applicant or Partner of a Joint Venture***

Applicants, including each partner of a joint venture, should provide financial information to demonstrate that they meet the minimum requirements that the lead partner shall meet not less than 40 percent of all qualifying criteria and each of the partners shall meet not less than 25 percent of all the qualifying criteria given in Evaluation Criteria. All the above figures will be added together to arrive at JV's total capacity. Each applicant or partner of a joint venture must fill-in this form. If necessary, use separate sheets to provide complete banker information. A copy of the audited balance sheets should be attached.

<b>Banker</b>	Name of banker	
	Address of banker	
	Telephone	Contact name and title
	Fax	Telex

Summarize actual assets and liabilities in Pak Rupees (Equivalent at the current rate of exchange at the end of each year) for the previous five years, based upon known commitments, projected assets and liabilities in pak Rupees equivalent for the next two years.

Financial information in Pak Rs. or equivalent	Actual: previous five year					Projected next two years	
	1	2	3	4	5	6	7
1. Total assets							
2. Current assets							
3. Total liabilities							
4. Current liabilities							
5. Profits before taxes							
6. Profits after taxes							

Specific proposed sources of financing to meet the cash flow of the Project, net of current commitments

Source of financing	Amount (Pak Rs. or equivalent)
1.	
2.	
3.	
4.	

Attach audited financial statements for the last five years (for individual applicant or each partner of joint venture). Firms owned by individuals, and partnerships, may submit their balance sheets certified by a registered accountant, and supported by copies of tax returns, if audits are not required by the laws of their countries of origin in case of foreign firms.



## Check List

Yes	No	Check list
<input type="checkbox"/>	<input type="checkbox"/>	Valid PEC Certificate(s) in required category
<input type="checkbox"/>	<input type="checkbox"/>	Copy of valid dealer ship certificate
<input type="checkbox"/>	<input type="checkbox"/>	Application form (A-1), General Information
<input type="checkbox"/>	<input type="checkbox"/>	Application form (A-2), General Experience Record
<input type="checkbox"/>	<input type="checkbox"/>	Application form (A-3), Joint Venture Summary
<input type="checkbox"/>	<input type="checkbox"/>	Application form (A-4), Particular Experience (Record List of Solar based pumping machinery projects of similar nature and complexity completed in last five years and complexity in-hand.)
<input type="checkbox"/>	<input type="checkbox"/>	Application form (A-5), Detail of Contracts of Similar Nature and Complexity (Supply & Installation of Solar based pumping machinery)
<input type="checkbox"/>	<input type="checkbox"/>	Application form (A-6) Current Contract Commitments/Works in Progress
<input type="checkbox"/>	<input type="checkbox"/>	Application form (A-7), Personnel Capabilities
<input type="checkbox"/>	<input type="checkbox"/>	Application form (A-8) Candidate Summary (List of B.Sc. Engineers having relevant experience with their CVs and PEC Reg. No.& List of Associates Engineers (DAE) with their CVs having relevant experience )
<input type="checkbox"/>	<input type="checkbox"/>	Application form (A-9), Equipment capabilities
<input type="checkbox"/>	<input type="checkbox"/>	Application form (A-10), Financial Capability
<input type="checkbox"/>	<input type="checkbox"/>	Application form (A-11), Litigation History
<input type="checkbox"/>	<input type="checkbox"/>	Undertaking that all equipment listed in this document for qualification will be made available for the subject Project
<input type="checkbox"/>	<input type="checkbox"/>	Audited balance sheets for at least last three years and Bank statements
<input type="checkbox"/>	<input type="checkbox"/>	Undertaking that the Applicant has not been declared bankrupt
<input type="checkbox"/>	<input type="checkbox"/>	Original affidavit that the firm has not been black listed
<input type="checkbox"/>	<input type="checkbox"/>	Applicants legal status
<input type="checkbox"/>	<input type="checkbox"/>	Principal place of Business
<input type="checkbox"/>	<input type="checkbox"/>	Place of incorporation or registration
<input type="checkbox"/>	<input type="checkbox"/>	Certificate of registration with Income Tax & Sales Tax Department
<input type="checkbox"/>	<input type="checkbox"/>	Enlistment record with Government organizations and other agencies
<input type="checkbox"/>	<input type="checkbox"/>	Location of workshop facility, if any
<input type="checkbox"/>	<input type="checkbox"/>	Equipment's sole agencies represented by the Contractor
<input type="checkbox"/>	<input type="checkbox"/>	Written description of internal quality control program for specified works

## EVALUATION CRITERIA

### 1.1 Eligibility for Qualification

Keeping in view the complexity of the Project, eligibility of Applicants for qualification evaluation is as mentioned below:

Sr. No.	Description	Yes/No
1.	Registration with Pakistan Engineering Council (PEC) in relevant category with field of specialization EE-11 <b>(Specified for Solar Energy)</b>	If "YES" the applicant will be Eligible for further Evaluation for qualification (copy of valid PEC certificate shall be attached).
2.	Blacklisting from any Government/Semi-Government Agency/Department.	If "YES" the applicant will not be Eligible for further Evaluation for qualification. (Original Affidavit on Judicial Stamp Paper that the firm has not been black listed from any Government/ Semi Government Agency/ Department till date shall be provided).
3.	System Design	System Design must be submitted in technical bid otherwise applicant will not be Eligible for further Evaluation.
4.	<ul style="list-style-type: none"> <li>i. Firm must have ISO 9001-2008 certificate quality management system</li> <li>ii. Firm must have pumping machinery according to ISO 9906 Roto dynamic acceptance test.</li> <li>iii. Warranty period for solar panel etc will be 20 years and pumping machinery 2 – years for electrical/mechanical parts.</li> <li>iv. Firm must have 100 Million Accumulative turnover for last 3 Years in Solar Pumping System. Must be attached Sales Tax Returns, Income Tax Returns &amp; Financial Audited Balance Sheets.</li> <li>v. Goods declaration (bill of entry) must be provided for each product (i.e Solar Panel, Pumps, Motors, Inverter &amp; Tracker Sleeve Drive).</li> <li>vi. Performance curves at STC for both solar panel and pumping machinery</li> </ul>	Attach Valid documents

	should be provided for each work separately along with bidding documents	
	vii. The PV modules offered should not be more than One (01) year old with respect to the date of manufacturing.	
	viii. Brand name(s) of PV modules, the supplier intends to supply must be included in the technical proposal.	
	ix. Solar Manual Tracker slow speed DC Motors driven.	
	x. Defect liability period of Electrical / Mechanical work will be 2 years.	

## 1.2 Evaluation Criteria

Keeping in view the complexity of the Project works, criteria for qualification has been evolved by considering the prevailing market trends as mentioned below:

<b>Sr. No.</b>	<b>Category</b>	<b>Weightage/Marks</b>
i.	General Capabilities	10
ii.	Financial Soundness	20
iii.	Experience Record	30
iv.	Personnel Capabilities	20
v.	Equipment Capabilities	20
Total:		100

Qualification will be carried out on the point scoring basis. Any applicant securing overall minimum score of 60 % as total will be considered as qualified.

An applicant may score below 60% in any one category provided it is not less than 50%.

Applicants having score of less than 60% in any two categories shall not be considered for further evaluation.



## Qualification Evaluation Criteria

### i) General Capabilities

a)	Copy of Valid dealer ship(pumps & solar panels) certificate from Sub-Contractor/JV Partner	2	<ul style="list-style-type: none"> <li>No marks will be given if license is not attached and 2 points will be added in case of valid certificate.</li> </ul>
c)	Litigation History in which Decision has been given against the firm(s)	6	<ul style="list-style-type: none"> <li>In case the firm is involved in any litigation, -5 will be given and 6 points will be added in case original affidavit of no litigation is attached.</li> </ul>
d)	Description of Internal Quality Control assurance program for Construction/ Erection/Maintenance	2	<ul style="list-style-type: none"> <li>2 Marks will be given if Description is provided.</li> </ul>
<b>Total Marks Allocated</b>			<b>10</b>

### ii) Financial Soundness

Sr. No.	Description	Marks Assigned	Criteria for Marks Obtained
a)	Bank Certificate including Bank Credit Line (Evidence in Original from Guarantor Bank)	5	<p><b><u>Bank Certificate (2-Marks)</u></b></p> <ul style="list-style-type: none"> <li>2 Marks are given if Original Bank Certificate is provided.</li> </ul> <p><b><u>Bank Credit Line (3-Marks)</u></b></p> <ul style="list-style-type: none"> <li>2 Marks are given if the available bank credit line limit is equal to 10 Million.</li> <li>For limit less than 10 Million, use following weight-age: <math>2 \times (A/50)</math></li> <li>For the limit more than 10 million but less than 20 million use following weight-age:</li> </ul>

			<p><math>2 + (A/100)</math></p> <p>A = Available Bank Credit Line Limit</p> <ul style="list-style-type: none"> <li>• Full Marks are given in case of limit is 20 million or more.</li> </ul>
b)	Audited Balance Sheets for at least last three years	5	<ul style="list-style-type: none"> <li>• No marks will be given if Audited Balance Sheets are not attached. Two (2) points will be given for one year audited balance sheets, four (4) points for two years and full points for three years.</li> </ul>
c)	Working Capital in last 5 years	5	<ul style="list-style-type: none"> <li>• 3 Marks are given if the available average working capital for last three years is equal to 25 Million.</li> <li>• For the capital less than 25 million use following weight-age: <math>3 \times (A/50)</math></li> <li>• For the capital more than 25 million but less than 50 million use following weight-age: <math>3 + (A/100)</math></li> </ul> <p>A = Average working capital in last three years.</p> <ul style="list-style-type: none"> <li>• Full Marks are given in case of limit is 50 million or more.</li> </ul>
d)	Registration with income tax & sale tax department	5	<ul style="list-style-type: none"> <li>• No marks will be given if NTN&amp; GST Registration certificate is not attached and 5 points will be added in case of valid certificates.</li> </ul>
<b>Total Marks Allocated</b>			<b>20</b>

iii) **Experience Record**

Sr. No.	Description	Marks Assigned	Explanation for Marks Obtained
a)	Projects of similar nature and complexity 4.0 Million each (Supply & Installation of Solar Based Pumping Machinery) completed in last five years in any Public Works Department/NGOs.	16	<ul style="list-style-type: none"> <li>• 8 Marks are given if the applicant has completed at least 5 projects of similar nature in last five years.</li> <li>• For less than 5 projects completed use the following weight age. <math>8 \times (A/5)</math></li> <li>• For more than 5 projects but less than 10 projects completed use the following weight age. <math>8 + (A/5) \times 4</math> A = No of projects of similar nature completed in last five years</li> <li>• Full Marks are given in case of 10 projects or more.</li> </ul>
b)	Projects of similar nature and complexity 4.0 Million each (Supply & Installation of Solar Based Pumping Machinery) in-hand in any Public Works Department/NGOs.	9	<ul style="list-style-type: none"> <li>• 4 Marks are given if the applicant has completed at least 5 projects of similar nature in last five years.</li> <li>• For less than 5 projects completed use the following weight age. <math>4 \times (A/5)</math></li> <li>• For more than 5 projects but less than 10 projects completed use the following weight age. <math>4 + (A/10) \times 4</math> A = No of projects of similar nature completed in last five years Full Marks are given in case of 10 projects or more.</li> </ul>
c)	Enlistment record with Government Organizations & other agencies	5	<ul style="list-style-type: none"> <li>• 1 Mark for each enlistment up to maximum of five enlistments.</li> </ul>
<b>Total Marks Allocated</b>			<b>30</b>

iv) **Personnel Capabilities**

<b>Sr. No.</b>	<b>Description</b>	<b>Marks Assigned</b>	<b>Explanation for Marks Obtained</b>
i)	B.Sc. Engineers registered with Pakistan Engineering Council (PEC)	14	<p><b><u>Experience (6-Marks)</u></b></p> <ul style="list-style-type: none"> <li>6 Marks will be given if the individual relevant experience of at least 1 numbers of B.Sc. Engineer Electrical/Electronics/Mechanical (professional) is equal to 15 years or above.</li> </ul> <p><b><u>Strength of Engineers (8 Marks)</u></b></p> <ul style="list-style-type: none"> <li>4 Marks will be given if the total no. of Engineers registered with PEC is 3.</li> <li>8 Marks will be given if the total no. of engineers registered with PEC is 5 or above.</li> </ul>
ii)	Associates Engineers (DAE)	6	<p><b><u>Experience (4-Marks)</u></b></p> <ul style="list-style-type: none"> <li>4 Marks will be given if the individual relevant experience of at least 1 number of Associates Engineers Electrical/Mechanical (DAE) is equal to 8 years or above.</li> </ul> <p><b><u>Strength of Associate Engineers (2 Marks)</u></b></p> <ul style="list-style-type: none"> <li>2 Marks will be given if the total no. of Associate Engineers (DAE) are 3 or above.</li> </ul>
<b>Total Marks Allocated</b>			<b>20</b>

**v) Equipment Capabilities**

<b>Sr. No.</b>	<b>Description</b>	<b>Marks Assigned</b>	<b>Explanation for Marks Obtained</b>
a)	1. Test Bed for verification / testing of Solar pumps along with all accessories as per ISO-9906 in company premises. (Firm must have Third Party Certification regarding Test Bed arrangements).	13	13 Marks for complete setup are given. (Attached Third Party Certificate)
b)	Workshop facilities. Attach layout sketch of workshop.	5	No marks will be given if Contractor has no workshop facilities.
c)	Equipment sole agencies represented by the Contractor	2	1 mark for each agency Upto maximum 2 points
<b>Total Marks Allocated</b>			<b>20</b>

**Appendix C to  
Instructions to Bidders**

**Domestic Goods (Value added in Pakistan)**

NOT USED

## **SPECIFICATION FOR THE SUPPLY AND INSTALLATION OF SOLAR BASED PUMPING UNITS**

### **1. SOLAR PANELS:**

#### **1.1 Solar cell type:**

The photovoltaic cell should use technology of Mono Crystalline Silicon Cell with high efficiency and the w module efficiency should be minimum 17% or above. More power per square meter than other panel. Low temperature coefficient. The PV modulus have an ability to works well with high voltage input inverter/charger controllers (1000 Vdc). Fully automated production cycle, reducing sources of variation in production, Manufacturer should have their own in house solar cell and solar panel manufacturer facility. Multi award winning company should preferred.

#### **1.2 Protections:**

Panel should have series fuse rating of 15 Amp with a bypass diodes for reverse current protection. Junction box should be there with water resistant capability. Ingress protection of panel should be at least IP-65. Cable connectors should be ingress protected by at least IP-67 with application classification of class A. Panel should have capability to sustain its functionality with wind load of at least **3.8 KPa** & Robust frame up to **5400 Pa** snow load. Ammonia and salt mist corrosion resistance.

#### **1.3 Material & finishing:**

The encapsulation material must be Ethylene Vinyl Acetate (EVA) and its lamination with temperature safety glass. Special glass etching and anti-reflective coating.

#### **1.4 Traceability:**

A strip containing Serial number should be laminated inside the module so as to be clearly visible from front side.

#### **1.5 Life Time and Warranty:**

The PV cells should be designed for more than 25 years of its life with power decrease of not more than 20% after completion of 20 years. Solar panel should have at least 20 years of guarantee with all its subsystem. The PV module offered should not be more than one (01) year old with respect to the date of manufacturing. Unique Serial No of PV Modules and date (DD/MM/YYYY) of manufacturing should be laminated inside of the module to make it clearly visible from the front side. Brand name of PV modules, the supplier intends to supply must be included in the technical proposal.

#### **1.6 Wiring:**

Panel wire should be specifically designed for solar usage with Plug and play connectors. Wiring should have compatibility of field serviceable contact removal.

#### **1.7 PID Free Certification:**

Potential Induced Degradation (PID) refers to potential induced performance degradation in crystalline photovoltaic modules. It occurs when the module's voltage potential and leakage current cause ion mobility within the module. The degradation accelerates with exposure to humidity, temperature and voltage potential. Consequently, PID can have a profound adverse effect on the financing and operation of PV plants. PID tests simulate the practical conditions in the PV system, and verify the module performance and power output under high voltage and temperatures.

#### **1.8 Standard Conformity:**

The PV module should fully conform to following specifications.

- IEC 61215-1 : 2016
- IEC 61215-1-1 : 2016
- IEC 61215-2 : 2016

- IEC 61730-1 : 2016
- IEC 61730-2 : 2016
- IEC-61701(latest).
- IEC-62716.
- IEC-60068-2-68.
- PPP58042

### **1.9 Submittals:**

Following details should be provided in Technical Bid otherwise bidder will not eligible for further evaluation:

- PID Free Certificate from TUV.
- TUV certification of IEC-61215:2016 and IEC-61730: 2016 Conformity.
- I-V curve for solar photovoltaic module panel.
- PV module efficiency at STC.

Note: All above mentioned certificate must be provided for offered panel and all information regarding solar panel with above mentioned featured data,EL and Flush test report from manufacturer for each panel should be accessible and verifiable online on manufacturer website or verifiable in writing from the manufacturer through fast track courier.

## **2. INVERTER/CONTROLLER:**

The solar pump controller should have built-in MPPT controller, Voltage Frequency (V/F) regulation, over load protection, soft start/ soft stop features and variable frequency Drive (VFD) with integrated Gate Bipolar transistors. The make and origin of the inverter/controller should be of Japanese and European origin or approved equivalent and clearly mentioned in the technical proposal. The inverter offered should comply to or equivalent standards:

- CE/ROHS/international standards (ISO 14001, OHSAS 18001 applicable).
- Low Voltage Directive 2014/35/EU with supplements.
- EMC Directive 2004/108/EU with supplements.
- The efficiency of inverter should be 92% and above.
- Inverter should have at least three (3) years extendable to 10 years' performance warranty.

### **2.1 Inverter circuit must include protection against:**

- Over or low voltages and currents beyond critical level of the inverters circuits.
- Protection against accidental short circuits & reverse polarity connections.
- Over load protection.
- Low RPM protection (i-e: efficiency < 30 Hz) Motor should be stop.
- Dry run protection.

### **2.2 Submittals:**

Following details should be provided with the tender submission.

- LVD certificate
- Origin country Certificate for module quality
- CE marking
- Test report for weather-Proof Test (IP65)

The complete datasheet showing all the electrical parameters like input & output voltage ranges should be provided in the technical bid.



### 3. MOUNTING STRUCTURE:

The panel mounting structure should be made of hot dipped galvanized steel pipes, or epoxy coated mild steel pipes (minimum wall thickness 2.5 mm) and should have the provision for vertical (east to west) automatic Sun-Tracking by slewing drive. A sketch of the mounting frame showing dimensions of the frame parts should be provided in the technical proposal.


### 4. Manual TRACKING SYSTEM: (As per BOQ).

The tracker offered should be fabricated from GI pipes or channels having minimum wall thickness of 2.6 mm. It should have large mounting capacity 4000 Wp to 5500 Wp in order to achieve better land area utilization. The tracker offered should have robust structure capable of withstanding 150 km/hr wind speed. The tracker structure should rest on standard 9-Inch gear drive/ slewing drive having following minimum specifications. Three years' comprehensive free replacement, repair and maintenance warranty (Free of cost) should be provided for all components of Manual tracker (including Batteries).

Detail catalog showing material specifications, load characteristics, make & origin of the slewing Drive and rated speed, voltage and power of the DC motor used must be provided in the Technical Proposal.


<i>Slewing Drive Performance Data</i>		
Rated Output Speed	0.049 rpm	
Rated Output Torque	805.2 kN.m	595.8 lbf.ft
Tilting Moment Torque (Max.)	33.9 kN.m	25×10 <sup>3</sup> lbf.ft
Holding Torque	38.7 kN.m	29×10 <sup>3</sup> lbf.ft
Axial Load (Max.)	338 kN	76×10 <sup>3</sup> lbf
Radial Load (Max.)	135 kN	30×10 <sup>3</sup> lbf
Ratio of Worm Gear	61:1	
Tracking Precision	≤ 0.17°	


The tilting moment/ axial load characteristics should meet or exceed the following



The slewing drive offered should be maintenance free. The drive control should be

fully autonomous and based on real time sun sensing (not timer based control). There should be safety limit switches to restrict the movement of tracker. The control should have protection for tracker overloading due to jamming and or other reason. There should be provision for manual movement of tracker. Reference drawings showing concrete plan, general dimensions and slewing drive size are enclosed herewith.





General Dimensions and Concrete Plan of Single Pole PV Mounting Structure with Single Axis Tracking System

Sr. No.	Type/Size	X (ft)	Y (ft)	H1 (ft)	H2 (ft)	a	A (ft)	B (ft)	D (ft)	a (ft)	b (ft)	d (ft)	C (in)	H (ft)	h (ft)
1	5/72x20	20.7	13.25	>3	12	30-36	4	4	5.5	2	2	1	8	4.5	4
2	5/72x21	18.5	15.55	>3	12	30-36	4	4	5.5	2	2	1	8	4.5	4
3	6/60x18	19.52	16.10	>3	12	30-36	4	4	5.5	2	2	1	8	4.5	4
4	6/60x20	21.5	16.27	>3	12	30-36	4	4	5.5	2	2	1	8	4.5	4

### **5. SYSTEM DESIGN/SIZING:**

De-rating factors should be applied while designing the system in order to have compensations for variations in irradiance. The motor output (BHP) should be at least **20%** more than the pump required input power (Shaft Power). Also the panel peak power at STC ( $W_p$ ) should be **50%** more than the maximum required input power of the motor (motor consumption).

### **6. PRE-SUPPLY TESTING & INSPECTION:**

The firm applying for the tender must have test bed facility to carry out pump performance acceptance test witnessed by third party inspector/Client as per ISO-9906 standard. Each of the offered pump set models must undergo this witness test prior to supply and installation.

### **7. DC CABLE / WIRING:**

99% copper wires of size at least 6 mm for single and 6 mm or above for multi strings and rated current 30A to be used. Working temperature range should be in between -40C to +85C. The cable must have double insulation suitable for 1000 VDC transmission, and all the relevant test reports i.e.

- Conductor resistance test.
- Insulation resistance test.
- Pressure test.
- Spark test.

Are to be provided in the technical proposal. The wiring must be protected by PVC conduits for underground installations. DC circuit breakers (not fuse) of at least 800V and suitable ampere rating must be installed between PV modules and PV pump controller in order to avoid short-circuiting. No direct jointing in DC power line is allowed, junction boxes of at least IP-44 rating are to be used for easy debugging where necessary. The cable should have safety level class II and standard flame class. Shell protection degree should be IP67 with connector rating IP67 (plug and play). The insertion and withdrawal force up to 50N can be bearable by the cable.

The Supplier should provide the manufacturer quality tests certificates at the time of supply.

## **SPECIFICATIONS FOR PUMPING MACHINERY AS PER ISO-9906 STANDARD**

### **1. PUMP:**

Pumps are to be supplied having standard ISO-9906 specifications. The pump must be submersible, made of stainless steel. The characteristic curves showing the efficiency and performance of the pumps are to be provided in the technical proposals. The quoted pump is to be tested for its performance and certified as per ISO-9906 standard. The pump must be suitable for installation and operation in tube wells/dug wells/open well with clear water discharge. Pump shall comprise of bowl assembly and non-return valve as integral part of pump's parts. Pump and motor shall rigidly couple through NEMA standard coupling. The stage casings of pumps should be connected as per NEMA/ANSI/AWWA/ASTM/BSS standard. Each stage casing must have replaceable wear ring. The impellers shall be secured to the pump shaft with tapered conical sleeves pressed into the taper bore of impeller or impeller secured through chrome plated stainless steel hexagonal sleeves. Suction casing must be between pump and motor with suction strainer as protection of pump against coarse impurities of the liquid handled.

Specification for Main Components of the Pumps:

**1.1 CASING/DIFFUSER:** The Casing/Diffuser should be in fabricated stainless steel AISI 304.

**1.2 IMPELLERS:** stainless steel AISI 304

**1.3 DRIVING SHAFT:** Stainless steel 304/420

**1.4 SLEEVES:** Stainless steel AISI 329/ 304

**1.5 GASKETS:** Rubber Gaskets

**1.6 BEARINGS:** AISI 329 stainless steel

**1.7 COUPLING & SCREEN + CABLE GUARD:** Stainless steel AISI 316/319/304/420

**1.8 NON-RETURN VALVE:** As per British standard specifications (BSS), Minimum 16 bar pressure sustaining design

**1.9 PRESSURE GAUGE:** As per British standard specifications (BSS), having PSI or Bar scale

**1.10 CLAMPS:** Steel – Pressed

**1.11 PUMP EFFICIENCY:** Minimum efficiency of the pump should be 70% at duty point

### **2. MOTOR:**

The origin, make and material of the motor should be clearly mentioned in the technical proposal. The winding material should be 99.99% copper. The motor should have wet type, water cool rewind-able/repairable stator. The motor should have non-disposable/non-hermetically sealed winding. The insulation class of the winding material should be mentioned. For each model quoted, all the technical parameters such as rated voltage, power factor, efficiency, full load ampere, speed and other similar parameters should be provided in the technical proposal. The testing report with all basic parameters should also be provided at the time of supply.

The motor shall be manufactured in compliance with National Electrical Manufacturer Association (NEMA) standards. The motor shall be three-phase submersible and shall be capable of operating at rated voltage of 380 Volts at 50 Hz. The motor should be capable of operating with variable speed through V/F control. Winding of the motor shall of rewind able type with class – IC40 insulation and IP68 protection. The

synchronous speed should be 2850-2950 RPM. Motor shall be capable of operating in well water with temperature starting from 40C. Motor should be designed for continuous operation. Motor must be filled with water without any chemical additives hazardous to health, for cooling. The motor must be properly protected against the entry of well water sand etc. by double mechanical seal i.e. one rotating and other stationary and the seal must be made of Silicon carbide/ Tungsten carbide and must be protected with sand protection guards. All supports shall be high grade cast iron and stator outer side jacket body should be in stainless steel in AISI 304. The excessive pressure due to heating up of the filled water must be compensated by a pressure equalizing rubber diaphragm in the lower part of the motor. The axial thrust of the pump shall be countered by oscillating sliding block type thrust bearing. The thrust bearing of the motor should be able to bear a download thrust force from the water pump and the upward thrust force produced while starting the water pump. Motor shall be capable of minimum of 20 starts in an hour. Motor efficiency should not be less than 70%.

Material/technical specifications of rewind-able wet stators, three phase squirrel cage water filled submersible motor.

**2.1 WINDING:** Made of pure electrolyte copper a non-hygroscopic poly vinyl chloride for normal temperature and must full fill resistant tests range.

**2.2 STATOR:** Energy efficient low-losses electrical magnetic sheet should be fixed in stainless steel casing. M800 or M600 magnetic sheet are preferable to use.

**2.3 ROTOR:** Energy efficient low-losses electrical magnetic sheet fixed with high grade copper bars. M800 or M600 magnetic sheets are preferable to use.

**2.4 SPLINE SHAFT:** AISI 420 stainless steel, flange dimension according to NEAM standard, over size design to ensure stiffness n severs condition.

**2.5 SHAFT BEARING:** Water lubricated guide/general bearings fixed in upper and lower brackets should be made of metal impregnated carbon.

**2.6 LOWER THRUST BEARING:** Thrust sliding block bearings, self-aligning Mitchell type, should be able withstand 15500N/20000N axial load.

**2.7 MECHANICAL SEAL (STATIONARY & ROTARY):** Silicon carbide or tungsten carbide mechanical seal.

**2.8 COOLING FILLING FLUID:** Water mixed with non-toxic anti-freeze provides cooling and lubrication also protect and prevent inside parts from corrosion.

**2.9 DEGREE OF PROTECTION:** IP68

**2.10 INSULATION OF CLASS:** Class B.

**2.11 VOLTAGE TOLERANCE:** -6% to -10%

**2.12 MOUNTING POSITION:** Vertical horizontal

**2.13 Class:** IC40

**2.14 MAXIMUM IMMERSION:** 150 Meters

**2.15 STATING PER HOUR:** 20

### **3. SUBMERSIBLE FLAT ELECTRIC CABLE:**

The submersible cable should be made of 99% copper coated with double PVC, should be adequately flexible and environment friendly. The cable must have undergone quality tests as per BSS standards. Following lab tests are mandatory.

- Conductor resistance test.
- Insulation resistance test.
- Pressure test.
- Spark test.

Note: The Supplier should provide the manufacturer quality tests certificates at the time of supply.

### **4. COLUMN PIPE:**

The column pipe shall be flanged ERW steel pipes confirming to ASTM designation A-53 with a minimum thickness of 3.5 mm and shall be painted with corrosion resistance paint of suitable thickness. Flanges thickness of 20 mm shall have grooves for cable passage. Each column pipe shall be complete with gaskets, bolts/studs, washers and nuts. All nuts, bolts, and washers shall be made of minimum A2 grade stainless steel.

The column pipe shall be supplied in interchangeable section having an approximate length of 10 feet. The flanges should be welded perfectly perpendicular to the axis of the pipe.

FEATURES:

- Manufacturer's pipes should meet international standards like BSEN 10255 &ASTMA 53.
- Dimensional accuracy circularity and plan end cut should be observed,
- Weld strength of pipe and mechanical properties or raw material should be tested as per manufacturing standards.
- Pipes should be NDT tested (Non-destructive – Eddy current)
- Pipes should be tested for hydrostatic pressure as per manufacturing standard.
- Pipes should be gone through straightening process to remove bendiness.

### **5. TOP SET:**

Top set shall comprise of Bore covers plate, (covering bore hole completely and securely), installation/suspension clamps, sluice valve, reflex valve, connector and cable jointing material (Cable connection from motor to switching device shall be joint free) pressure gauge and cable ties.

## **SPECIFICATION FOR THE SUPPLY AND INSTALLATION OF SOLAR BASED LIGHTING SYSTEM**

The bidders are also required to supply and install solar system with battery backup for lighting up the pump premises and ceiling fan in operator room. The specifications for the major components of the system are as under:

### **1. PV Modules:**

(As described in the specifications for supply and installation of solar based pumping units.)

**2. Charge Controller:** MPPT charge controller of suitable ampere rating, with battery over charge/ discharge protection.

### **3. Battery:**

**3.1 Battery Type:** The battery offered should be maintenance free and VRLA/ GEL/ AGM type

### **3.2 Technical Features:**

- Real front-access terminal connections for fast and easy installation and maintenance
- Easy on easy off multi-purpose design terminal protector
- Suitable for 19", 23" racking or cabinet
- Micro-porous glass mats in low resistance as separator
- Flame retardant ABS material container and cover compliant with UL94 V-0
- Self-regulating pressure relief valve
- Self-discharge rate: < 2% per month at 77°F (25°C)
- Design life: more than 12 years at 68°F (20°C)
- Shelf life: 6 months at 68°F (20°C)
- Valve regulated system, no water addition needed

**3.3 Compliant standards:** The battery offered should comply with:

- IEC 60896-2
- BS 6290 Part 4
- Telcordia SR-4228
- EUROBAT GUIDE
- UL

**4. FLOOD LIGHTS:** The lights offered should have single LED with at least 80 Lumens per watt. The lights offered should have IP-66 enclosure.

**5. DC WIRING:** As described in the specifications for supply and installation of solar based pumping units.







GOVERNMENT OF KHYBER PAKHTUNKHWA,  
KHYBER PAKHTUNKHWA  
PUBLIC PROCUREMENT REGULATORY AUTHORITY

Peshawar, the May 10, 2022 / 6058-21

**NOTIFICATION**

**S.R.O. (14)/Vol: 1-24/2021-22:** In exercise of the powers conferred under Section 35-A of the Khyber Pakhtunkhwa Public Procurement Regulatory Authority Act, 2012 (Khyber Pakhtunkhwa Act No. XI of 2012) the Authority has been pleased to issue the following regulation, namely: -

1. **Short title and commencement.-** (i) This regulation may be called the Khyber Pakhtunkhwa Public Procurement Regulation No. XIV 2022.  
(ii) This shall come into force at once.
2. **Matters pertaining to Additional Security in case of abnormally low bids.-** This regulation relates to the matters pertaining to Additional Security submitted by the bidders in procurement of works.
  - i. The contractors quoting their bids up to a limit of 10% below Engineer estimate shall submit bid security @ 2% only of Engineer Estimate.
  - ii. The contractors quoting their bids more than 10% below upto 20% below on Engineers' Estimate shall submit along with their bids 8% Additional Security of Engineer's Estimated cost in addition to 2% bid security. If the bid is not accompanied with the required amount of additional security then it will be considered as non-responsive and the 2% bid security shall be forfeited in favour of Government and the second lowest bidder and so on will be considered accordingly.
  - iii. [Similarly, a contractor quoting bid more than 20% below shall submit with his bid an additional security on Engineer's Estimated cost equal to the differential amount of submitted bid and Engineers' Estimate along with detailed rate analysis]<sup>1</sup>. In case of more than 20% below bids, if the bid is not accompanied by the detailed rate analysis and / or required amount of additional security, then the said bid shall be considered as non-responsive. All the securities submitted along with such non-responsive bid shall be forfeited in favour of Government and the 2<sup>nd</sup> lowest bidder and so on will be considered accordingly.
  - iv. In case detailed rate analysis submitted with the bids is, in view of the Procuring Entity, not convincing, the Head of the Procuring Entity may declare such bid as non-responsive without any forfeiture of bid securities and record reasons thereof.
  - v. The procuring entity may offer the contract to next lowest bidder after due diligence in the context of financial difference between such two bids or may advertise procurement opportunity afresh.

<sup>1</sup> Differential amount; if a contractor quote, e.g. 25% below engineer estimate bid then he has to deposit along with his bid 2% bid security and 25% additional security of engineer estimate.

- vi. After commencements of work by the successful bidder, the procuring entity may replace the Additional Security with a bank guarantee of the same amount from the scheduled bank; if the already deposited security is not in the form of bank guarantee.
- vii. The Additional Security shall be released to the contractor in four installments i.e. 1<sup>st</sup> installment of 25% to be released upon completion of 25% of the project, 2<sup>nd</sup> installment of 25% to be released upon completion of 50% of the project, 3<sup>rd</sup> installment of 25% to be released upon completion of 75% of the project and the 4<sup>th</sup> installment of 25% to be released after 100% completion of the project.
- viii. All previous orders, instructions and regulations issued regarding additional security shall stand superseded.

-SD-  
Managing Director  
KPPRA

**ENDST: No. As above:**

**Peshawar, the May 10, 2022**

**Copy forwarded to:-**

1. The Additional Chief Secretary (P&D) Department, Govt. of Khyber Pakhtunkhwa.
2. The Administrative Secretaries (C&W, Irrigation, Public Health Engineering and Local Government, Elections & Rural Development Department) Khyber Pakhtunkhwa with request to circulate the same to their downstream formations for compliance.
3. The Principal Secretary to Governor, Khyber Pakhtunkhwa.
4. The Principal Secretary to Chief Minister, Khyber Pakhtunkhwa.
5. The Inspector General of Police, Khyber Pakhtunkhwa.
6. The Secretary Provincial Assembly, Khyber Pakhtunkhwa.
7. The Accountant General, Khyber Pakhtunkhwa.
8. The Registrar, Peshawar High Court, Peshawar.
9. All Commissioners and Deputy Commissioners in Khyber Pakhtunkhwa.
10. PSO to Chief Secretary, Govt. of Khyber Pakhtunkhwa.
11. All Heads of Autonomous/Semi-Autonomous Bodies in Khyber Pakhtunkhwa.
12. Director, Treasuries & Accounts with request to circulate the same to all DAOs & Treasuries Officers in Khyber Pakhtunkhwa.
13. The Section Officer (Admn), Finance Department, Govt. of Khyber Pakhtunkhwa with respect to his office letter No. SO(A)/FD/1-40/2022, dated 22.04.2022.
14. Manager, Stationery and Printing Press Khyber Pakhtunkhwa, for printing in the official gazette.

  
SANA ULLAH  
Assistant Director (M&E), KPPRA